



Quote

From:

Speedy Line Marking Au PTY LTD
 16 Flack Avenue, Hillsdale
 NSW 2036
 info@speedylinemarking.com.au
 ABN 32 673 397 503

Quote Number	QUO-906
Quote Date	September 17, 2024
Total	\$5,995.00

To:

Bentleigh Group
 adminsupport4@bentleighgroup.com.au

Hrs/Qty	Service	Rate/Price	Sub Total
3	George st: redo floor logos George st car bay floors need to be redone with the new logo stencil Green paint to be supplied and white paint supplied Green squares to be recoated with trans-ocean green epoxy and re-stenciled with white logos. To be coated with a coat of white epoxy first. For the logos that have already used Dulux A1 Roadmaster to be washed off or removed before over-coating with white epoxy. All line marking to be applied in accordance with Australians standards	\$200.00	\$600.00

Thanks for choosing Speedy Line Marking | info@speedylinemarking.com.au

Terms and Conditions: Line marking to designated area as per specifications. **Please note the following points:**

Line marking is weather dependant, Area should not be driven over for a certain period, please refer to product specification for full details, Vehicles to be removed prior to attending site to complete works, Area to be clear of any obstacles which may impede line marking.



Hrs/Qty	Service	Rate/Price	Sub Total
1	<p>George st: redo logo & get rid of the 2 green horizontal line</p> <p>George st column logo needs to have the 2 green horizontal lines on logo filled in with white</p> <p>A1 Dulux road master (White)</p> <p>All line marking to be applied in accordance with Australians standards</p>	\$50.00	\$50.00
12	<p>Pitt st: redo floor logos</p> <p>George st car bay floors need to be redone with the new logo stencil</p> <p>Green paint to be supplied and white paint supplied</p> <p>Green squares to be recoated with trans-ocean green epoxy and re-stenciled with white logos. To be coated with a coat of white epoxy first.</p> <p>For the logos that have already used Dulux A1 Roadmaster to be washed off or removed before over-coating with white epoxy.</p> <p>All line marking to be applied in accordance with Australians standards</p>	\$200.00	\$2,400.00
8	<p>Pitt st: Column logo needs to be moved down so that the top of the green line is in line with the top of the bumper</p> <p>logo needs to have the 2 green horizontal lines on each logo filled in with white</p> <p>Green paint to be supplied</p> <p>A1 Dulux road master (White)</p> <p>All line marking to be applied in accordance with Australians standards</p>	\$200.00	\$1,600.00

Thanks for choosing [Speedy Line Marking](http://speedylinemarking.com.au) | info@speedylinemarking.com.au

Terms and Conditions: Line marking to designated area as per specifications. **Please note the following points:**

Line marking is weather dependant, Area should not be driven over for a certain period, please refer to product specification for full details, Vehicles to be removed prior to attending site to complete works, Area to be clear of any obstacles which may impede line marking.



Hrs/Qty	Service	Rate/Price	Sub Total
8	Pitt st: column logo where the green is above the yellow bumper on the column needs to be painted white on the columnC Match the white on the columns A1 Dulux road master (White) All line marking to be applied in accordance with Australians standards	\$100.00	\$800.00
1	Establishment Fees (INCLUDED FREE) All work to be conducted in accordance with Australian standards Speedy Line Marking to provide all insurance documents if required Speedy Line Marking to provide SWNS if required Speedy Line Marking to provide Certificate of Currency if required Speedy Line Marking to provide Company Registration if required	\$640.00	\$0.00

Sub Total	\$5,450.00
Tax	\$545.00
Total	\$5,995.00

Thanks for choosing [Speedy Line Marking | info@speedylinemarking.com.au](http://info@speedylinemarking.com.au)

Terms and Conditions: Line marking to designated area as per specifications. **Please note the following points:**

Line marking is weather dependant, Area should not be driven over for a certain period, please refer to product specification for full details, Vehicles to be removed prior to attending site to complete works, Area to be clear of any obstacles which may impede line marking.