

From:

Speedy Line Marking Au PTY LTD 16 Flack Avenue, Hillsdale NSW 2036 info@speedylinemarking.com.au ABN 32 673 397 503

Total	\$4,851.00
Quote Date	December 19, 2024
Quote Number	QUO-1081

To: Design build maintain megan@nswdbm.com.au

Hrs/Qty	Service	Rate/Price	Sub Total
1	'Keep Clear Area' Lettering - Hatching approx 50m x 3m - yellow - Chevron to be 45 degrees. 300mm wide. 300m gap - The perimeter of of the Keep Clear Box will be a 100mm line painted yellow A1 Dulux road master Antislip P5 agregate 2 years warranty All line marking to be applied in accordance with Australians standards	\$2,250.00	\$2,250.00

Thanks for choosing Speedy Line Marking | info@speedylinemarking.com.au

Terms and Conditions: Line marking to designated area as per specifications. **Please note**the following points:

Line marking is weather dependant, Area should not be driven over for a certain period, please refer to product specification for full details, Vehicles to be removed prior to attending site to complete works, Area to be clear of any obstacles which may impede line marking.



Hrs/Qty	Service	Rate/Price	Sub Total
1	Establishment fees (Night work) All work to be conducted in accordance with Australian standards Speedy Line Marking to provide all insurance documents if required Speedy Line Marking to provide SWNS if required Speedy Line Marking to provide Certificate of Currency if required Speedy Line Marking to provide Company Registration if required	\$960.00	\$960.00
1	Pressure washing the work area Power scrub/Pressure wash: Area to be chemically cleaned All work to be conducted in accordance with Australian standards	\$1,200.00	\$1,200.00

Total	\$4,851.00
Tax	\$441.00
Sub Total	\$4,410.00

Thanks for choosing Speedy Line Marking | info@speedylinemarking.com.au

Terms and Conditions: Line marking to designated area as per specifications. **Please note**the following points:

Line marking is weather dependant, Area should not be driven over for a certain period, please refer to product specification for full details, Vehicles to be removed prior to attending site to complete works, Area to be clear of any obstacles which may impede line marking.